



Contact Information

O: 480.317.1221
F: 480.968.8229
E: salessupport@wolffmechanical.com

Location

1701 S. Indian Bend Rd, Suite 101
Tempe, Arizona 85281
ROC91867 · ROC91873 · ROC282236

Proposal and Contract

Calvis Wyant - Sims Residence (480) 905-4217
10728 East Wingspan Way, Scottsdale, AZ 85255

2/1/2018

WOLFF MECHANICAL PROPOSES THE FOLLOWING SCOPE OF WORK:
DUCT DESIGN PER WOLFF MECHANICAL SPECIFICATIONS & STANDARDS; VENT DRYER, HOOK UP LOW VOLTAGE THERMOSTAT WIRE
SUPPLY AND INSTALL CONDENSATE PIPING; VENT RANGE HOOD; ALL DUCT TO BE HIGH QUALITY FOIL BACK FLEX WITH ALL DUCT IN
UNCONDITIONED SPACE INSULATED WITH R8, DUCT IN CONDITIONED SPACE INSULATED WITH R6 FURNISH GALVANIZED TEETOPS FOR
HVAC PENETRATIONS, ALL REGISTERS TO BE MULTI-LOUVERED, DAMPERED, AND FULLY DIRECTIONAL

Equipment (Sized per Manual J, 8th Edition, Heat Load Calculation meets all 2015 energy code requirements)

Daikin VRV-IV S Series w/ VRT Technology & True - Zoning System (No Extra Zoning Required):

Qty. 3	VRV-IV S-Series Outdoor Unit 4-Ton Condenser	
Qty. 10	Indoor Ducted / Ductless Units (7 Ducted Units & 3 Ductless Units)	
Qty. 9	Exhaust Fans & Vents for Laundry and Bathroom	
Qty. 1	Temperature Controlled Fan for AV Room	
		*Total Price: 72,857.00 USD
<u>Optional Upgrade:</u>		
Add MUA to Kitchen Range Hood		+ 1075.00 USD
Wine Unit		+ 7800.00 USD
AV Room 1-Ton Cooling Only (19 SEER)		+ 2500.00 USD

*Price includes 1 Ductless Indoor unit that conditions garage

Daikin Split System A/C with Heat pumps:

Qty. 1-	DZ16TC0481 4 Ton Condenser, DV61PTCD14 Air Handler, Honeywell Pro 8000 Redlink Thermostat (16 SEER)	
Qty. 1-	DZ16TC0361 3 Ton Condenser, DV37PTCD14 Air Handler, Honeywell Pro 8000 Redlink Thermostat (16 SEER)	
Qty. 3-	DZ16TC0241 2 Ton Condenser, DV31PTCC14 Air Handler, Honeywell Pro 8000 Redlink Thermostat (16 SEER)	
Qty. 2-	SkyAir Mini Split 1.5T Unit for Garage (SEER 18.6)	
Qty. 9-	Exhaust Fan with Vents for Laundry and Bathroom	
Qty. 1-	Temperature Controlled Fan for AV Room	
		*Total Price: 71,555.00 USD
<u>Optional Upgrade:</u>		
Add MUA to Kitchen Range Hood		+ 1075.00 USD
Wine Unit		+ 7800.00 USD
Add 4 Zone per System		+ 3500.00 USD
Add 3 Zone per System		+ 3000.00 USD
Add 2 Zone per System		+ 2500.00 USD
AV Room 1-Ton Cooling Only (19 SEER)		+ 2500.00 USD

Carrier Split System A/C with Heat pumps:

Qty. 1-	25HCB624A003 2 Ton Condenser, FV4CNF002L00 Fan Coil, Honeywell Pro 8000 Redlink Thermostat (17 SEER)	
Qty. 2-	25HCB636A003 3 Ton Condenser, FV4CNF003L00 Fan Coil, Honeywell Pro 8000 Redlink Thermostat (16 SEER)	
Qty. 2-	25HCB648A003 4 Ton Condenser, FV4CNB006L00 Fan Coil Honeywell Pro 8000 Redlink Thermostat (16 SEER)	
Qty. 1-	Mitsubishi 2.5T Unit for Garage (SEER 18)	
Qty. 9-	Exhaust Fan with Vents for Laundry and Bathroom.	
Qty. 1-	Temperature Controlled Fan for AV Room	
		*Total Price: 73,617.00 USD
<u>Optional Upgrade:</u>		
Add MUA to Kitchen Range Hood		+ 1075.00 USD
Wine Unit		+ 7800.00 USD
Add 4 Zone per System		+ 3500.00 USD
Add 3 Zone per System		+ 3000.00 USD
Add 2 Zone per System		+ 2500.00 USD
AV Room 1-Ton Cooling Only (18 SEER)		+ 2500.00 USD

Excludes 2015 Energy Code Requirements of Third Party, Independent Blower Door, Duct Blast Testing
General Contractor responsible to provide poured concrete pads for condensing units. This provides a stronger, cleaner, more durable base.

IF AZ5005 FORM NOT PROVIDED SALES TAX WILL BE CHARGED
STANDARD B-VENT IS INCLUDED FOR GAS HOT WATER HEATERS WHEN APPLICABLE, SPECIALIZED TANKLESS OR HIGH EFFICIENCY HOT WATER HEATERS REQUIRING PVC VENTING ARE NOT INCLUDED
PERMIT AND SALES TAX EXTRA IF REQUIRED. ADDITIONAL CHARGES REQUIRE WRITTEN SIGNED ORDERS, WORK DOES NOT INCLUDE ELECTRICAL, PLUMBING, CARPENTRY, CONCRETE WORK, GENERAL METAL OR UNDERGROUND RETURNS. EXCLUDES BONDS, BUILDING PERMITS, OR RETENTION. INFO DESIGN PROVIDED, EXCLUDES ENGINEERING, CERTIFIED AIR BALANCE, ABESTOS ABATEMENT, OVERTIME AND HOLIDAY WORK.

PAYMENT TERMS: Progressive Billing
WHEN EACH PHASE IS COMPLETE, PAYMENT IS EXPECTED PROMPTLY. OWNER/BUILDERS - TRIM IS C.O.D. PLEASE MAKE ARRANGEMENTS BEFORE TRIM CREW ARRIVES, OR TRIM CANNOT BE COMPLETED. 1.5% MONTHLY INTEREST ADDED TO ALL BALANCES OVER 30 DAYS
NOTE: CREDIT CARD PAYMENTS ARE ACCEPTED WITH A 5% SERVICE CHARGE ADDED TO TOTAL
APPROXIMATE COMPLETION TIME _____DAYS RI _____DAYS TRIM APPROXIMATE START DATE _____
ACCEPTANCE OF PROPOSAL: THE ABOVE PRICES, SPECIFICATIONS, AND CONDITIONS ARE SATISFACTORY AND ARE HEREBY ACCEPTED. YOU ARE AUTHORIZED TO DO THE WORK SPECIFIED.

CUSTOMER’S SIGNATURE _____ DATE _____

WOLFF MECHANICAL SIGNATURE _____ DATE _____

THIS IS A PROPOSAL ONLY. OFFER IS GOOD FOR 30 DAYS AND IS NOT VALID UNLESS SIGNED.
PROPOSAL BECOMES A CONTRACT ONCE SIGNED.
ALL MATERIAL IS GUARANTEED TO BE AS SPECIFIED. ALL WORK TO BE COMPLETED IN A SUBSTANTIAL WORKMANLIKE MANNER ACCORDING SPECIFICATIONS SUBMITTED PER STANDARD PRACTICES. ANY ALTERATIONS OR DEVIATIONS FROM ABOVE SPECIFICATIONS INVOLVING EXTRA COST WILL BE EXECUTED ONLY UPON WRITTEN ORDERS AND WILL BECOME AN EXTRA CHARGE OVER AND ABOVE THIS ESTIMATE. ALL AGREEMENTS ARE CONTINGENT UPON STRIKES, ACCIDENTS, OR DELAYS BEYOND OUR CONTROL. OWNER IS TO CARRY FIRE, TORNADO, AND OTHER NECESSARY INSURANCE. OUR WORKERS ARE FULLY COVERED BY WORKMAN'S COMPENSATION INSURANCE.